

Addendum

ADDENDUM NO. 1

Date: February 21, 2017

Re: Findlay Parking Lot Improvement
Owens Community College
Project No. **OTC01-17-FC-PRKGLOT**
30335 Oregon Road, Perrysburg, Ohio 43551

To: Bidders

This addendum forms a part of the contract documents and modifies the original Project description.

Acknowledge receipt of this addendum in the space provided on the bid form

GENERAL AND PROCUREMENT:

1. Revised project description
2. Alternates removed
3. Issued revised bid form.

SPECIFICATIONS (New or Re-issued):

BASE BID

Parking lot reconstruction: North half of parking lot, remove existing asphalt, excavated for new 10" total pavement thickness, compact subgrade, install 6" new 302 stone base (1650 tons) and pave with 2.5" of ODOT 448 type 2 Base asphalt and 1.5" of ODOT 448 type 1 surface asphalt.
All existing asphalt and spoils to be hauled off site.

Square footage of North half of the lot is 44,500 sq ft

4" underdrain including stone backfill and tie-ins extending from sidewalk on West side of parking lot 126' to the East side, tie-in to existing tile along East length of parking lot.

All spoils hauled off site.

Estimated: 1,180 Linear ft.

Stripe lot per original layout – one coat

Salvage existing stone base - This will be a credit item for salvaged existing stone base.

This quantity is based on salvaging 4" of existing stone.

Your total extension for this item should be a negative number or credit.

All stone tickets for new stone shall be turned in.
The final credit quantity will be based on
the 1650 tons of ITEM #1 stone minus total ticket tonnage installed.

END OF ADDENDUM #1